

**MATERIAL LIST**

**G1836A Garage Plan**

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	89.50	16"	67	EA
2	MAIN TREATED SILL		2X6			90	LF
3	MAIN EXT PLATES		2X6			288	LF
4	UPPER EXT STUDS		2X6	91.00	16"	81	EA
5	UPPER CEILING S.R. (Optional)		1/2" GYP.			648	SF
6	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			864	SF
7	HEADER, (Ext Main Garage Door)	B02	4X12	13'		1	EA
8	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
9	HEADER, (Main Window)	N/A	4X8	4'		1	EA
10	HEADER, (Upper Window)	N/A	4X8	4'		2	EA
11	HEADER, (Upper Window)	N/A	4X10	9'		1	EA
12	TRUSSES				24"	17	EA
13	TRUSSES (Ends)					2	EA
14	EAVE BLOCKING		2X	22.5"	24"	36	EA
15	H2.5 RAFTER TIE				24"	38	EA
16	ROOF SHEATH		1/2" CDX			850	SF
17	ROOF FELT		30# Felt			850	SF
18	ROOFING					850	SF
19	BARGE RAFTERS		2X6	12'		4	EA
20	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			720	SF
21	MAIN CEILING S.R. (Optional)		1/2" GYP.			648	SF
22	EXT WALL SHEATH		1/2" CDX			1584	SF
23	EXT WALL VAPOR		15# Felt			1584	SF
24	EXT SIDING (See Plan)		Varies			1584	SF
25	CONCRETE (Footing)		12" X 20"			6.67	CY
26	CONCRETE (Floor)		4"			8.00	CY
27	JOISTS	B01	2X12	18'	16"	28	EA
28	RIM JOIST					108	LF
29	UPPER FLOOR PLYWOOD		5/8"			648	SF
30	STAIR BEAM	B03	4X12	14'		1	EA
31	ANCHOR BOLTS		1/2"		48"	23	EA
32	HOLD DOWNS		HD5A W/ SSTB20			4	EA
33	WIRE MESH		6X6 W1.4 X W1.4			648	SF