

MATERIAL LIST G2020A Garage
w/truss attic

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		SIZE	LENGTH	DIST.	O.C.	QUANTITY	
1	EXT. STUD	2x4	102" (Varies)	61.0	16	46	EA
2	TREATED SILL	2x4		61.0		61	LF
3	PLATES	2x4		80.0		224	LF
4	DOOR HEADER	4 X 12	17			1	EA
5	HEADER	4 X 12	11'	4'+7'		1	EA
6	WALL S.R. (Optional)	1/2"		61		610	SF
7	CEILING S.R. (Optional)	1/2"				400	SF
8	FLOOR PLYWOOD	5/8"				200	SF
9	WALL SHEATH	1/2" CDX		61.0		810	SF
10	WALL VAPOR	15# Felt		61.0		810	SF
11	SIDING			61.0		810	SF
12	CONCRETE (Footing)	12" x 6"				1.48	CY
13	CONCRETE (Wall)	6" x 20"				2.47	CY
14	CONCRETE (Floor)	4"				4.89	CY
15	TRUSSES (Roof)		20' + O.H.	20	24	11	EA
16	ROOF SHEATH	7/16"				653	SF
17	ROOF FELT	30# Felt				653	SF
18	ROOFING	Composition				653	SF
19	EAVE BLOCKING	2X4	22.5"	40	24	21	EA
20	H2.5 RAFTER TIE			40	24	21	EA
21	HD8A (See Plan)					4	EA
22	SSTB28					4	EA

MATERIAL LIST

**G2020A Garage w/ Storage
Framed Roof**

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		CALC.	SIZE	LENGTH	O.C.	QUANTITY	
1	EXT. STUD		2x4	92" (varies)	16	46	EA
2	TREATED SILL		2x4			61	LF
3	PLATES		2x4			224	LF
4	HEADER, Garage Door	B04	5-1/8" X 12" GLB	20'	1	EA	
5	HEADER, Window	BO5	4 X 10	7		1	EA
6	WALL S.R. (Optional)		1/2" GYP.			549	SF
7	CEILING S.R. (Optional)		1/2" GYP.			400	SF
8	FLOOR PLYWOOD		5/8"			400	SF
9	WALL SHEATH		1/2" CDX			749	SF
10	WALL VAPOR		15# Felt			749	SF
11	SIDING (See Plan)					749	SF
12	CONCRETE (Footing)		12"x6"			1.48	CY
13	CONCRETE (Wall)		6" x 20"			2.47	CY
14	CONCRETE (Floor)		4"			4.89	CY
15	RAFTERS	BO2	2x6	17'	16	28	EA
16	ROOF SHEATH		7/16"			653	SF
17	ROOF FELT		30# Felt			653	SF
18	ROOFING		Composition			653	SF
19	EAVE BLOCKING		2X8	14.5"	16	31	EA
20	H2.5 RAFTER TIE				24	21	EA
21	RIM JOISTS		2X12			80	LF
22	FLOOR JOISTS	B03	2X12	20'	16	14	EA
23	RIDGE	B01	3-1/8"x15" GLB	20'		1	EA
24	KNEE WALL STUDS (Opt.)		2X4	6'	16	31	EA
25	KNEE WALL PLATES (Opt.)		2X4			40	LF
26	HD8A (See Plan)					4	EA
27	SSTB28					4	EA