

**MATERIAL LIST**

**G2224F Garage Plan**

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X4	95.5" (Varies)	16"	54	EA
2	MAIN TREATED SILL		2X6			73	LF
3	MAIN EXT PLATES		2X4			228	LF
4	HEADER, (Ext Main Garage Door)	B01	4X12	9'		2	EA
5	HEADER, (Ext Main Door)		4X8	4'		1	EA
6	HEADER, (Main Window)		4X8	5'		3	EA
7	TRUSSES				24"	10	EA
8	TRUSSES (Ends)					2	EA
9	EAVE BLOCKING		2X	22.5"	24"	22	EA
10	H2.5 RAFTER TIE				24"	24	EA
11	ROOF SHEATH		1/2" CDX			698	SF
12	ROOF FELT		30# Felt			698	SF
13	ROOFING					698	SF
14	BARGE RAFTERS		2X6	15'		4	EA
15	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			657	SF
16	MAIN CEILING S.R. (Optional)		1/2" GYP.			528	SF
17	WALL SHEATH		1/2" CDX			801	SF
18	WALL VAPOR		15# Felt			801	SF
19	SIDING (See Plan)		Varies			801	SF
20	CONCRETE (Footing)		12" X 20"			5.68	CY
21	CONCRETE (Stem)						CY
22	CONCRETE (Floor)		4"			6.52	CY
23	CONC. FOOTING, (Doorway Slab)		(1) 48" X 48" X 4" DP.			0.20	CY
24	ANCHOR BOLTS		1/2"		48"	19	EA
25	HOLD DOWNS		HD2A W/SSTB16			5	EA
26	WIRE MESH		6X6 W1.4 X W1.4			7	SF