

MATERIAL LIST

G2624E Garage Plan

Standard W/ Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	95.13	16"	59	EA
2	MAIN TREATED SILL		2X6			78	LF
3	MAIN EXT PLATES		2X6			184	LF
4	UPPER INT PLATES		2X4			48	LF
5	UPPER INT WALL STUDS		2X4	6'	16"	37	EA
6	UPPER S.R. (Optional)		1/2" GYP.			621	SF
7	HEADER, (Ext Main Garage Door)	B04	4X12	9'		2	EA
8	HEADER, (Ext Main Door)		4X8	4'		2	EA
9	HEADER, (Main Window)		4X8	4'		3	EA
10	HEADER, (Upper Window (Optional))	B03	3-1/8X9 GLB	5'		1	EA
11	RAFTERS	B02	2X10	21'	16"	38	EA
12	EAVE BLOCKING		2X	14.0"	16"	36	EA
13	H2.5 RAFTER TIE				16"	38	EA
14	ROOF SHEATH		1/2" CDX			1030	SF
15	ROOF FELT		30# Felt			1030	SF
16	ROOFING					1030	SF
17	BARGE RAFTERS		2X6	21'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			702	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			624	SF
20	EXT WALL SHEATH		1/2" CDX			702	SF
21	EXT WALL VAPOR		15# Felt			702	SF
22	EXT SIDING (See Plan)		Varies			702	SF
23	CONCRETE					13.62	CY
24	JOISTS	TJI	18 TJI 360	26'	16"	19	EA
25	RIM JOIST					100	LF
26	UPPER FLOOR PLYWOOD		5/8"			624	SF
27	STAIR BEAM	B05	3-1/8X13-1/2 GLB	26'		1	EA
28	RIDGE BEAM	B01	5-1/8X19-1/2 GLB	24'		1	EA
29	ANCHOR BOLTS		1/2"		48"	20	EA
30	HOLD DOWNS		HD2A W/SSTB16			6	EA
31	WIRE MESH		6X6 W1.4 X W1.4			624	SF

MATERIAL LIST

G2624E Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	95.13	16"	59	EA
2	MAIN TREATED SILL		2X6			78	LF
3	MAIN EXT PLATES		2X6			184	LF
4	UPPER S.R. (Optional)		1/2" GYP.			621	SF
5	HEADER, (Ext Main Garage Door)	B04	4X12	9'		2	EA
6	HEADER, (Ext Main Door)		4X8	4'		2	EA
7	HEADER, (Main Window)		4X8	4'		3	EA
8	HEADER, (Upper Window (Optional))	B03	3-1/8X9 GLB	5'		1	EA
9	TRUSSES				24"	11	EA
10	TRUSSES (Ends)					2	EA
11	EAVE BLOCKING		2X	22.5"	24"	24	EA
12	H2.5 RAFTER TIE				24"	26	EA
13	ROOF SHEATH		1/2" CDX			1030	SF
14	ROOF FELT		30# Felt			1030	SF
15	ROOFING					1030	SF
16	BARGE RAFTERS		2X6	21'		4	EA
17	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			702	SF
18	MAIN CEILING S.R. (Optional)		1/2" GYP.			624	SF
19	EXT WALL SHEATH		1/2" CDX			702	SF
20	EXT WALL VAPOR		15# Felt			702	SF
21	EXT SIDING (See Plan)		Varies			702	SF
22	CONCRETE					13.04	CY
23	UPPER FLOOR PLYWOOD		5/8"			624	SF
24	GIRDER TRUSS			26'		1	EA
25	ANCHOR BOLTS		1/2"		48"	20	EA
26	HOLD DOWNS		HD2A W/SSTB16			6	EA
27	WIRE MESH		6X6 W1.4 X W1.4			624	SF