

MATERIAL LIST

G2630F Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	93.50	16"	68	EA
2	MAIN TREATED SILL		2x6			91	LF
3	MAIN EXT PLATES		2X6			318	LF
4	UPPER EXT STUDS		2X6	91.00	16"	55	EA
5	UPPER EXT WALL PLATES		2X6			312	LF
6	UPPER CEILING S.R. (Optional)		1/2" GYP.			713	SF
7	UPPER EXT WALL S.R. (Optional)		1/2" GYP.			832	SF
8	HEADER, (Ext Main Garage Door)	B01	4X12	10'		2	EA
9	HEADER, (Main Window)	N/A	4X10	6'		1	EA
10	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
11	HEADER, (Upper Window)	N/A	4X8	4'		10	EA
12	TRUSSES				24"	12	EA
13	TRUSSES (Ends)					2	EA
14	EAVE BLOCKING		2X	22.5"	24"	30	EA
15	H2.5 RAFTER TIE				24"	32	EA
16	ROOF SHEATH		1/2" CDX			1009	SF
17	ROOF FELT		30# Felt			1009	SF
18	ROOFING					1009	SF
19	BARGE RAFTERS		2X6	16'		4	EA
20	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			819	SF
21	MAIN CEILING S.R. (Optional)		1/2" GYP.			780	SF
22	EXT WALL SHEATH		1/2" CDX			1715	SF
23	EXT WALL VAPOR		15# Felt			1715	SF
24	EXT SIDING (See Plan)		Varies			1715	SF
25	CONCRETE					16.31	CY
26	JOISTS	B02	18 TJI 360	26'	16"	23	EA
27	RIM JOIST					104	LF
28	UPPER FLOOR PLYWOOD		5/8"			676	SF
29	RAFTERS		2X6	6'		20	EA
30	JOISTS		2X6	4'		20	EA
31	ANCHOR BOLTS		1/2"		48"	23	EA
32	HOLD DOWNS		HD5A W/ SSTB20			4	EA
33	WIRE MESH		6X6 W1.4 X W1.4			780	SF