

UPPER

	ITEM	CALC	SIZE	LENGTH	DIST.	O.C.	QTY	
20	EXT. STUDS		2x6	96" (VARIES)	117	16	88	EA
21	EXT WALL PLATES		2x6		120		120	LF
22	JOISTS	TJI	16" TJI 560	28	32	16	25	EA
23	RIM JOIST		16"X1-3/4 LVL		120		120	LF
24	FLOOR PLYWOOD		3/4" PLY				896	SF
25	HEADER, Door			4			1	EA
26	HEADER, Window	B02	4X8	4			3	EA
27	RIDGE BEAM	B01	5-1/8 X 15 GLB	14			1	EA
28	RIDGE BEAM	B01	5-1/8 X 15 GLB	14			1	EA
29	RAFTERS	B09	2x12	25	56	12	58	EA
30	ROOF SHEATH		1/2"				1442	SF
31	ROOF FELT		30# Felt				1442	SF
32	ROOFING		Composition				1442	SF
33	EAVE BLOCKING		2X	10.5	56	12	56	EA
34	H2.5 RAFTER TIE				56	12	58	EA
35	WALL S.R. (Optional)				306		2448	SF
36	CEILING S.R. (Optional)		1/2" GYP.				1346	SF
37	INT WALL STUDS		2x4	VARIES	96	16	73	EA
38	INT PLATES		2x4		96		288	EA
39	DORMER RIDGE BM	B04	(2)2X12	12'			2	EA
40	DORMER RFTRS		2X12	8'	12	16	22	EA
41	DORMER DOUBLE RFTRS	B07	VARIES	24'			4	EA
42	DORMER VALLEY RFTRS		2X12	8'			4	EA
43	DORMER TRIMMERS	B08	(2)2X12	8'			2	EA
44	STAIR BEAM	B05	PT 2X12	12'			1	EA
45	STAIR BEAM	B06	PT (2)2X12	12'			1	EA