MATERIAL LIST G3030A Garage w/ Storage above

Framed Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

		CALC	SIZE	LENGTH	DIST.	O.C.	QTY	
1	EXT. STUD		2x6	9' (varies)	99.00	16	75	EA
2	TREATED SILL PLATE		2x6		99.00		99	LF
3	PLATES		2x6		120.00		360	LF
4	HEADER, Garage Door	B04	3-18X12 GLB	10			2	EA
5	HEADER, Garage Door	B05	3-18X12 GLB	7			1	EA
6	MAIN WALL S.R. (Optional)		1/2" GYP.		99		990	SF
7	CEILING S.R. (Optional)		1/2" GYP.				900	SF
8	FLOOR PLYWOOD		5/8"				900	SF
9	WALL SHEATH		1/2" CDX		99		990	SF
10	WALL VAPOR		15# Felt		99		990	SF
11	SIDING (See Plan)				99		990	SF
12	CONCRETE (Footing)		12"x6"				2.22	CY
13	CONCRETE (Stem Wall)		6" x 20"				3.70	CY
14	CONCRETE (Floor)		4"				11.00	CY
15	RAFTERS	BO2	2X12	22'	30	16	46	EA
16	FLOOR JOISTS	TJI	(SEE PLAN)	30'	30	16	23	EA
17	ROOF SHEATH		1/2"				1089	SF
18	ROOF FELT		30# Felt				1089	SF
19	ROOFING		Composition				1089	SF
20	EAVE BLOCKING		2X12	14.5"	60	16	44	EA
21	H2.5 RAFTER TIE				60	16	46	EA
22	RIDGE	B01	5-1/8x21 GLB	30'			1	EA
23	RIM JOIST		(SEE TJI)		120.00		120	LF

22685 S.W. Conifer Dr.
Sherwood OR 97140

Internet: www.cadnw.com
Email: cadnw@zzz.com

(503) 625-6330 Voice