

MATERIAL LIST

G3030F Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	113.50	16"	70	EA
2	MAIN TREATED SILL		2X6			94	LF
3	MAIN EXT PLATES		2X6			300	LF
4	UPPER CEILING S.R. (Optional)		1/2" GYP.			1172	SF
5	HEADER, (Ext Main Garage Door)	B01	3-1/8X13-1/2 GLB	8'		1	EA
6	HEADER, (Ext Main Garage Door)	B02	6-3/4X16-1/2 GLB	17'		1	EA
7	HEADER, (Ext Main Door)	N/A	4X8	4'		2	EA
8	HEADER, (Upper Window)	N/A	4X8	4'		2	EA
9	HEADER, (Main Window)	N/A	4X12	3'		1	EA
10	TRUSSES				24"	14	EA
11	TRUSSES (Ends)					2	EA
12	EAVE BLOCKING		2X	22.5"	24"	30	EA
13	H2.5 RAFTER TIE				24"	32	EA
14	ROOF SHEATH		1/2" CDX			1416	SF
15	ROOF FELT		30# Felt			1416	SF
16	ROOFING					1416	SF
17	BARGE RAFTERS		2X6	22'		4	EA
18	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			940	SF
19	MAIN CEILING S.R. (Optional)		1/2" GYP.			900	SF
20	EXT WALL SHEATH		1/2" CDX			940	SF
21	EXT WALL VAPOR		15# Felt			940	SF
22	EXT SIDING (See Plan)		Varies			940	SF
23	CONCRETE (Footing)		12" X 6"			4.22	CY
24	CONCRETE (Stem)		6" X 20"			3.70	CY
25	CONCRETE (Floor)		4"			11.11	CY
26	UPPER FLOOR PLYWOOD					501	SF
27	POST		6X6	10'		8	EA
28	POST		4X4	10'		2	EA
29	DORMER, (Ridge Beam)	B03	2X12	13		2	EA
30	RAFTERS	N/A	2x6	7	24"	18	EA
31	DORMER, (Rafters)	N/A	2X6	6		28	EA
32	DORMER, (Joists)	N/A	2X6	7		30	EA
33	DORMER, (Trimmer)	B05	2X12	7		2	EA
34	ANCHOR BOLTS		1/2"		48"	24	EA
35	HOLD DOWNS		HD5A W/ SSTB20			4	EA
36	WIRE MESH		6X6 W1.4 X W1.4			900	SF