

MATERIAL LIST

G3040B Garage Plan

Standard W/ Truss Roof

This estimate is designed solely to provide the customer with a rough estimate of the amount of material used in the given project. The material estimate is based on normal and typical building and construction techniques. The actual amount of material used may vary from this estimate due to a number of factors. Consequently, no representation or warranty has been made that the amount of material used will not vary from the estimate.

	ITEM	CALC	SIZE	LENGTH	O.C.	QTY	
1	MAIN EXT STUDS		2X6	101.50	16"	90	EA
2	MAIN TREATED SILL		2X6			121	LF
3	MAIN INT PLATES		2X6			18	LF
4	MAIN EXT PLATES		2X6			404	LF
5	MAIN INT STUDS		2X6		16"	6	EA
6	UPPER CEILING S.R. (Optional)		1/2" GYP.			680	SF
7	HEADER, (Ext Main Garage Door)	B01	4X12	17'		1	EA
8	HEADER, (Ext Main Door)	N/A	4X8	4'		1	EA
9	HEADER, (Main Window)	N/A	4X8	4'		2	EA
10	HEADER, (Ext Upper Door)	N/A	4X8	4'		1	EA
11	TRUSSES				24"	19	EA
12	TRUSSES (Ends)					2	EA
13	EAVE BLOCKING		2X	22.5"	24"	40	EA
14	H2.5 RAFTER TIE				24"	42	EA
15	ROOF SHEATH		1/2" CDX			1503	SF
16	ROOF FELT		30# Felt			1503	SF
17	ROOFING					1503	SF
18	BARGE RAFTERS		2X6	19'		4	EA
19	MAIN EXT WALL S.R. (Optional)		1/2" GYP.			1089	SF
20	MAIN INT WALL S.R. (Optional)		1/2" GYP.			108	SF
21	MAIN CEILING S.R. (Optional)		1/2" GYP.			1200	SF
22	EXT WALL SHEATH		1/2" CDX			1089	SF
23	EXT WALL VAPOR		15# Felt			1089	SF
24	EXT SIDING (See Plan)		Varies			1089	SF
25	CONCRETE					23.82	CY
26	UPPER FLOOR PLYWOOD		5/8"			1200	SF
27	GIRDER TRUSS	N/A		30'		1	EA
28	ANCHOR BOLTS		1/2"		48"	31	EA
29	HOLD DOWNS		HD2A W/SSTB16			4	EA
30	WIRE MESH		6X6 W1.4 X W1.4			1200	SF
31	JOISTS @ STAIR		2X6	4'		12	EA
32	RAFTERS @ STAIR		2X6	4'		8	EA